

# Operational Environmental Management Plan (OEMP) for the Fuel Station on Erf 1889, Extension 7 in Rundu, Kavango East Region



SEPTEMBER 2024

**PREPARED FOR**  
New Limit Property Developers CC

**PREPARED BY**  
Urban Green Sustainability Consultants



## PROJECT DETAILS

TITLE: Operational Environmental Management Plan (OEMP) for the Fuel Station on Erf 1889, Extension 7 in Rundu, Kavango East Region

REPORT NO: UG/2021-KEHEMUFS/OEMP-PHASE 3

STUDY PHASE: Operational Monitoring

REPORT DATE: September 2024

REPORT STATUS: Approved

PROPONENT	CONSULTANT
New Limit Property Developers CC	Urban Green Sustainability Consultants
PO Box 778, Rundu	PO Box 11929, Klein Windhoek
Email: <a href="mailto:norton@krcg.net">norton@krcg.net</a> & <a href="mailto:norton@nluis.net">norton@nluis.net</a>	Email: <a href="mailto:brand@urbangreenafrica.net">brand@urbangreenafrica.net</a>
Cell No. +264 (0) 816764919 Tel: +264 (0) 66 267 222	Tel: +264 – 61 – 300 820 Cell No.: +264 (0) 81 129 5759
Physical Address: Erf 1889, Extension 7 (Kehemu location) in Rundu, Namibia	Physical Address: Berg Street No. 40, Elysium Field Complex, Klein Windhoek, Namibia
	EAP's Signature: 

**OEMP REVISION STATUS**

Version	Date Approved	Revision Details
V1 – Original EMP	April 2017	
V2 – Updated OEMP	July 2021	
V3 – Updated OEMP	September 2024	Signed: 

## **TABLE OF CONTENTS**

PROJECT DETAILS  
OEMP REVISION  
STATUS GLOSSARY

### **LIST OF FIGURES**

#### **PART 1: OVERVIEW**

<b>1</b>	<b>OVERVIEW.....</b>	<b>1</b>
1.1	PROJECT BACKGROUND.....	1
1.2	PURPOSE OF THE EMP .....	1
1.3	ENVIRONMENTAL ASSESSMENT PRACTITIONER (EAP).....	2
1.4	LEGAL REQUIREMENTS.....	2
1.5	ASSUMPTIONS AND LIMITATIONS .....	4
1.6	REPORT STRUCTURE .....	4
<b>2</b>	<b>ROLES AND RESPONSIBILITIES.....</b>	<b>5</b>
2.1	PROPONENT’S REPRESENTATIVE.....	5
2.2	ENVIRONMENTAL CONTROL OFFICER .....	6
<b>3</b>	<b>ENVIRONMENTAL MANAGEMENT PLAN ACTIONS.....</b>	<b>6</b>
3.1	KEY POTENTIAL ENVIRONMENTAL IMPACTS TO BE MANAGED.....	6
3.2	PHASE 1: PLANNING AND DESIGN MANAGEMENT ACTIONS.....	7
3.3	PHASE 2: CONSTRUCTION PHASE MANAGEMENT ACTIONS.....	9
3.4	PHASE 3: OPERATION AND MAINTENANCE MANAGEMENT ACTIONS.....	14
3.5	PHASE 4: DECOMMISSIONING MANAGEMENT ACTIONS.....	15
3.6	RECOMMENDATIONS FOR MONITORING.....	15
<b>4</b>	<b>CONCLUSIONS .....</b>	<b>16</b>

### **LIST OF FIGURES**

#### **PART 1: OVERVIEW**

1.1	INTRODUCTION	1
1.2	THE CONSTRUCTION ENVIRONMENTAL MANAGEMENT PLAN (CEMP)	1
1.2.1	Environmental Management Plans	1
1.2.2	Scope of the CEMP	1

1.2.3	Format of the CEMP	2
1.2.4	Amendments to the CEMP	3
1.3	THE KEHEMU SERVICE STATION DEVELOPMENT	3
1.4	BRIEF OVERVIEW OF THE ENVIRONMENTAL PROCESS FOLLOWED	6
1.5	THE PROJECT	7

## **PART 2: COMPLIANCE MONITORING**

2.1	APPOINTMENT OF ENVIRONMENTAL SITE MANAGER (ESM)	8
2.2	IMPLEMENTATION OF THE CEMP	8
2.3	PROJECT DIVISION PLAN (PDP)	8
2.4	HOLISTIC INTEGRATED SYSTEMS	9
2.5	RECORD KEEPING	9
2.5.1	Site Instruction Entries	9
2.5.2	ESM Diary Entries	10
2.5.3	Method Statements	10
2.5.4	Monthly Monitoring Reports	10
2.5.5	Other Documents	10
2.6	ENVIRONMENTAL AWARENESS TRAINING	11
2.6.1	Environmental Site Manager	11
2.6.2	Environmental Awareness Course	11
2.7	CONSTRUCTION MONITORING	12
2.8	NON COMPLIANCE AND PENALTIES	12
2.9	ENVIRONMENTAL COMPLETION STATEMENT	13
2.10	ROLE PLAYERS AND THEIR RESPONSIBILITIES	14
2.10.1	Environmental Forum	14
2.10.2	Responsibilities of the ESM	14
2.10.3	Responsibilities of the Developer	16

2.10.4	Responsibility of the Engineer	16
2.10.5	Responsibilities of the Environmental Site Manager/s	16
2.10.6	Responsibilities of the Landscape Architect/Biologist/Ecologist	16
2.11	EMERGENCY PREPAREDNESS	17
2.12	FINANCING OF ENVIRONMENTAL CONTROL	17
2.13	DISPUTES AND DISAGREEMENTS	17
2.14	POST-CONSTRUCTION ENVIRONMENTAL AUDIT	17

### **PART 3: ENVIRONMENTAL SPECIFICATIONS**

3.1	SCOPE	18
3.2	CONSTRUCTION	18
3.2.1	Fencing	21
3.2.2	Access Routes	22
3.2.3	'No-go' Areas	26
3.2.4	Protection of Natural Features	28
3.2.5	Protection of Indigenous Fauna and Flora	28
3.2.6	Erosion and Sedimentation Control	28
3.2.7	Safety	32
3.2.8	Fire Control	33
3.2.9	Emergency Procedures	33
3.2.10	Community Relations	34
3.2.11	Construction Personnel Information Posters	34
3.3	MATERIALS	35
3.3.1	Hazardous Substances	35
3.3.2	Handling, Use and Storage of Construction Materials	35
3.3.3	Plant Material	36
3.4	CONSTRUCTION PLANT	37

3.4.1	Fuel and Oil	37
3.4.2	Ablution Facilities	39
3.4.3	Eating Area	39
3.4.4	Solid Waste Management	39
3.4.5	Waste Water Management	40
3.4.6	Workshop, Equipment Maintenance and Storage	40

3.4.7	Noise	41
3.4.8	Dust	42
3.4.9	Lights	42
3.4.10	Site Structures	43
3.4.11	Groundwater	43
3.5	POST CONSTRUCTION	43
3.5.1	Ripping of Compacted Soil	43
3.5.2	Site Rehabilitation	43
3.6	COMPLIANCE WITH REQUIREMENTS AND PENALTIES	43
3.6.1	Penalties	44
3.6.2	Penalty Fines	45
3.6.3	Removal from Site and Suspension of Works	45
3.7	MEASUREMENT AND PAYMENT	46
3.8	MITIGATION MEASURES AND PROPOSED MANAGEMENT PROGRAMME	46

APPENDIX A - ENVIRONMENTAL METHOD STATEMENT

APPENDIX B - PRO-FORMA: ENVIRONMENTAL MONITORING REPORT

APPENDIX C - LIST OF APPROVED PLANT SPECIES

APPENDIX D - DECLARED INVASIVE ALIEN SPECIES





# **PART 1: OVERVIEW**

## **1.1 INTRODUCTION**

During 2021 an application for the Transfer of Environmental Clearance Certificate (ECC-01935) ownership was approved by the DEA and therefore, ownership changed from the previous proponent, Norton Luis Consultants to the current New Limit Property Developers CC.

The Project entails the operations and maintenance (Phase 3) of a fuel station situated on Erf 1889, Extension 7 (of the Kehemu location) in Rundu.



Figure: 1.1 – Locality of Erf 1889, Kehemu, Rundu

During the construction phase, earthwork was carried out in certain areas of the project site to install the necessary services infrastructure, in line with the Environmental Management Act (Act 7 of 2007) and Environmental Assessment (EA) which was initially conducted by GCS Water and Environmental Consultants during 2017.

The activities undertaken at Erf 1889, Ext 7, Rundu, consist of the fuel retail building with ancillary services, two underground fuel storage tanks (23 m<sup>3</sup>) of unleaded petrol, and the provision of additional space alongside the tank farm for the installation of additional tanks in future (if required), fuel dispensing islands inclusive of pump island servicing equipment and forecourt furniture. Furthermore, the fuel station also comprises fuel dispensing island canopy, water/oil separator suitably located for ease of connections, high density Polyethylene (HDPE) fuel delivery pipeline system and tanks fitted with submersible pumps and ancillary equipment (automatic tank gaging etc.).

The components of the fuel station include dispensing islands fitted with fuel dispensers for pressure system and connections to municipal services. The fuel station has a 24-hour convenience (quick) shop. In terms of Civil and structural design and layout for site, kerb lines, concrete hard standing areas and containment slabs, layer works and appropriate forecourt and surrounding surfacing (where required), road marking, subsurface spill containment drainage system to interceptor and subsurface storm water system.

The site is bordered by tarred roads to the north and west and has three existing access points, of which two (northeast and east) enable vehicle access whereas the third access point (southwest) is only suitable for people on foot. The national water utility, NamWater supplies bulk water from the Okavango River to the Rundu Town Council, which provides the water to its customers (i.e. Rundu residents). The electricity system in the town is run by the Northern Regional Electricity Distributor (NORED). There is a variety of business activities within the town. For security, traffic and police officers are presents 24 hours in the town and many of the shops are having their own security guards. Rundu is connected to the rest of the national roads' network via B8, B10 and C45 main roads. There are tarred and gravel roads within the town.

has been developed, which included roads and storm water, underground power lines, water reservoir and water pipelines, as well as sewage treatment plant with reticulation network and effluent storage dam.

## **1.2 THE OPERATION ENVIRONMENTAL MANAGEMENT PLAN**

### **1.2.1 Operation Environmental Management Plans**

The purpose of the Operation Environmental Management Plan (EMP) is to provide management actions of the OEMP to avoid potential impacts where possible. Where impacts cannot be avoided, mitigation measures are provided to reduce the significance of these impacts. The management actions are compiled based on the project phase.

As such the OEMP provides specifications that the Managers and their personnel must adhere to, to minimize adverse environmental impacts associated with operational and monitoring activities. The Developer to which authorization was granted, is ultimately responsible for overall environmental performance.

The guidelines for the execution of an OEMP include the following:

- Employees appointed for operation and maintenance on respective site infrastructure and services must ensure that all personnel are aware of necessary health, safety and environmental considerations applicable to their respective work.
- The ECO or the Proponent should monitor the implementation of this OEMP.
- The ECO(s) should inspect the site operation throughout the operation on a biannual basis.
- Business facilities should be connected to municipal sewage systems and wastewater discharge systems and be in good working conditions to avoid groundwater contamination

in the case of leakages from sewage systems.

- No wastewater / effluent should be allowed to leave the site premises without proper control. These should be disposed of in accordance with municipal wastewater discharge standards.
- The tank observation wells (TOWs) which are installed around the fuel station to detect possible pollution from the tanks in groundwater should be monitored.
- Regular maintenance and monitoring of underground storage tanks should be done to detect early spills or leakages.
- An emergency plan should be available for major or minor spills at the service station during operation activities (with consideration of air, groundwater, soil and surface water)
- Groundwater impact awareness training should be provided for the employees involved in this phase 3.
- Fuel station workers should be provided with awareness training about the risks associated with fuel handling and storage.
- The fuel station facility should be equipped with fire extinguishers.
- During maintenance, workers should be properly equipped with personal protective equipment (PPE) such as coveralls, gloves, safety boots, safety glasses etc.

### **1.2.2 Scope of the CEMP**

In order to ensure a holistic approach to operational management and monitoring of environmental impacts during the operations of Phase III, this OEMP sets out the methods by which proper environmental monitoring are to be implemented by the ECO and all other. The following activities are in place, in terms of infrastructure and service provision:

- Potable water pipelines;
- Wastewater disposal pipelines; and
- Electrical cables for power supply.

Solid waste generated is removed on a regular basis and disposed at the Rundu Town Council solid waste management facility.

This OEMP intends to guide and manage the managing and monitoring activities within the activity site and surrounding areas as they relate to the natural environment. It describes mitigation measures, which must further be seen as open-ended, requiring regular review and updating via the correct channels to effectively guide operational environmental management of this project.

The provisions of this OEMP are binding on the ESO. Any third party appointed by the business manager in terms of the operations must comply with the conditions of this OEMP.

This EMP has been designed to suit the business activities and needs of development, and incorporates the following:

- Employee OEMP training and awareness measures;
- Specific project monitoring measures;
- Groundwater pollution mitigation measures;
- Specifications with which the ESM; and
- The health and safety risks are associated with the handling of highly flammable and hazardous products.

The OEMP is a dynamic document subject to similar influences and changes that are created by variations to the provisions of the project specification. Any substantial changes shall require the approval of the Environmental Forum.

### **1.2.3 Amendments to the CEMP**

During 2021 an application for the Transfer of Environmental Clearance Certificate (ECC-01935) ownership was approved by the DEA and therefore, ownership changed from the previous proponent, Norton Luis Consultants to the current New Limit Property Developers CC.

Any party involved with the Project can suggest changes to the OEMP via the ESO and Business Manager. Such suggestions will be presented to the Environmental Forum before approval and implementation. Approved changes will be minuted and drafted into this existing OEMP in the form of an appendix or amendments. This should be clearly stipulated in the OEMP to avoid confusion (see EMP Revision).

### **1.2.4 LAND USE AND INFRASTRUCTURE**

The Erf 1889 site is within the Rundu Townlands and is zoned as “business”. The erf is under the ownership of the Proponent (New Limit Property Developers CC). The area surrounding the fuel station shows a larger variety of land uses, which includes a supermarket, a taxi rank, an open market and various other institutional, small businesses and residential activities. The taxi rank is used by local taxi drivers who transport passengers from Rundu to destinations such as Kayengona, Shambyu etc. on the eastern side of the site.

## **PART 2: OPERATIONAL MONITORING COMPLIANCE**

### **2.1 MONITORING METHODOLOGY**

The on-site monitoring done by the IEO was done as per the requirements and stipulations of the OEMP (July 2021). This entailed an evaluation of the on-site activities as on the day against the requirements presented in Sections 3 & 4 of the Project OEMP (July 2021).

### **2.2 MONITORING REPORTING**

The findings are presented in the checklists below Tables 3.1 & 3.2, which include comments which the Proponent and/or Site Operator must comply with, if any.

Copies of the documents described below must be maintained on site at all times, to be provided on request to authorities or stakeholders for inspection. Operators' meeting minutes must reflect environmental queries, agreed actions and dates of eventual compliance.

#### **2.2.1 CONCLUSION**

The Site Manager's Site Office, the area accommodating the Fuel Station and directly surrounded areas has been managed well within the requirements of the OEMP. The operational activities have been executed in accordance with best practice principles at all times and compliance with Namibia legal requirements and environmental standards.

#### **2.2.2 Monthly Monitoring Reports**

Copies of the monthly monitoring reports compiled by the ESM should be kept on site for inspection.

#### **2.2.3 Other Documents**

A list of other reports to be kept on site is -

- All communications detailing changes of design/scope that may have environmental implications.
- Occupational Health and Safety reports.
- Complaints register.
- Incident and accident reports.
- Emergency preparedness and response plans.
- Crisis communication manual.
- All relevant permits.

## **2.3 EMERGENCY PREPAREDNESS**

The ESM shall compile and maintain environmental emergency procedures to ensure that there will be an appropriate response to unexpected or accidental actions or incidents that will cause environmental impacts, throughout the operational period. Such activities may include, inter alia:

- Accidental discharges to water and land.
- Accidental exposure of employees to hazardous substances.
- Accidental fires.
- Accidental spillage of hazardous substances.
- Accidental toxic emissions into the air.
- Specific environmental and ecosystem effects from accidental releases or incidents.

These plans shall include:

- Emergency organization (manpower) and responsibilities, accountability and liability.
- A list of key personnel and contact details.
- Details of emergency services available (e.g. the fire department, spill clean-up services, etc.).
- Actions to be taken in the event of different types of emergencies.
- Incident recording, progress reporting and remediation measures required to be implemented.
- Information on hazardous materials, including the potential impact associated with each, and measures to be taken in the event of accidental release.

### **3.1.1 Fire Control**

No fires may be lit on site. Any fires that occur shall immediately be reported to the ESM.

Smoking shall not be permitted in those areas where it is a fire hazard. Such areas shall include the workshop and fuel storage areas and any areas where the vegetation or other material is such as to make liable the rapid spread of an initial flame. Cigarette butts must be disposed of in designated containers.

In terms of the Atmospheric Pollution Prevention Act (No. 45 of 1965), burning is not permitted as a disposal method.

The ESM shall appoint a competent fire safety officer who shall be responsible for ensuring immediate and appropriate actions in the event of a fire and shall ensure that employees are aware of the procedure to be followed. The ESM shall ensure that there is basic fire-fighting equipment (e.g. fire buckets, extinguishers, fire beaters, etc.) available on Site at all times. This shall include at least rubber beaters when working in urban open spaces and one fire extinguisher of the appropriate type when welding or other “hot” activities are undertaken.

### **3.1.2 Emergency Procedures**

The ESM's procedures for the following emergencies shall include:

(i) Fire

- The ESM shall inform all relevant parties of a fire as soon as one starts and shall not wait until it can no longer be controlled.
- The ESM shall ensure that his employees are aware of the procedure to be followed in the event of a fire.

(ii) Accidental Leaks and Spillages

- The Manager shall ensure that his employees are aware of the procedure to be followed for dealing with spills and leaks, which shall include notifying the ESM and Resident Engineer.



- The business Manager shall ensure that the necessary materials (e.g. chemcap, spill-sorb, drizzat pads, enretech and sand buckets) and equipment for dealing with spills and leaks are available on Site at all times.
- The source of the spillage shall be isolated. The Manager shall contain the spillage using sand berms, sandbags, pre-made booms, saw dust or absorbent materials. Treatment and remediation of the spill areas shall be undertaken to the reasonable satisfaction of the ESM and Resident Engineer.

### **3.1.3 Hazardous Substances**

Petroleum, chemicals, harmful and hazardous waste shall be stored in an enclosed and bunded area. This area shall be subject to the approval of the Engineer. The waste shall be disposed of at a hazardous waste disposal site as approved by the ESM.

## **3.2 CONSTRUCTION PLANT**

### **3.2.1 Fuel and Oil**

If so required, fuel may be stored on Site in a depot complying with the requirements listed below. Where reasonably practical, construction vehicles and equipment shall be refuelled at the depot or at the workshop as applicable. The surface under the refuelling area shall be protected (bunded) against pollution to the satisfaction of the Resident Engineer and ESM prior to any refuelling activities.

The Manager shall ensure that there is always a supply of absorbent material (e.g. chemcap, spill-sorb, drizzat pads, enretech and peat moss) readily available to neutralize and where possible be designed to encapsulate minor spillage. The quantity of such materials shall be able to handle a minimum of 200 l of liquid spill.

#### **(i) Fuel storage areas**

- The ESM and Resident Engineer shall be advised of the area that the Contractor intends using for the storage of fuel. Fuels shall be stored at a suitable location inside the Contractor's Camp.
- The fuel storage area must not be located near (i.e. less than 100m) any water resource, including a river, stream or surface water body, or borehole.
- The Contractor shall ensure that all liquid fuels (petrol and diesel) are stored in tanks with lids, which are kept firmly shut.
- The tanks shall be situated on a smooth impermeable surface (250 µm plastic or concrete) base with an earth bund (plastic must have a 5cm layer of sand on top to prevent perishing). The impermeable lining shall extend to the crest of the bund and the volume inside the bund shall be 110% x the total capacity of all the storage tanks.
- The floor shall be bunded and sloped towards a sump to contain any spillages of substances. The bund shall be inspected and emptied daily, and serviced when

necessary. The bund shall be closely monitored during rain events to ensure that it does not overflow.

- The Manager shall keep fuel under lock and key at all times. No smoking shall be allowed in the vicinity of fuel tanks.
- The ESM shall educate workers on the appropriate methods for workshop maintenance and fuel points to prevent fuel and oil being washed out of containment areas.
- Only empty and externally clean tanks may be stored on the bare ground. All empty and externally dirty tanks shall be sealed and stored on an area where the ground has been protected. In addition, if fuel is dispensed from 200 l drums, the proper dispensing equipment shall be used, and the drum shall not be tipped in order to dispense fuel. The dispensing mechanism of the fuel storage tank shall be stored in a waterproof container when not in use.
- Symbolic safety signs depicting “No Smoking”, “No Naked Lights” and “Danger” are to be provided, and are to conform to the requirement of SABS 1186.
- The product contained within the tank shall be clearly identified; using the emergency information system detailed in SABS 0232 part 1.
- Any electrical or petrol-driven pump shall be equipped and positioned, so as not to cause any danger of ignition of the product.
- Areas for storage of fuels and other flammable materials shall comply with standard fire safety regulations and may require the approval of the fire safety officer.
- The Contractor shall ensure that there is adequate fire-fighting equipment at the fuel stores and that staff are adequately trained to use this equipment.

(ii) Fuel storage tanks

- Temporary above ground storage tanks may be permitted at the discretion of the ESM and Resident Engineer based on the merit of the situation, provided that the following requirements are met:
- All such tanks are to be designed and constructed in accordance with a recognized Act and code (Petroleum Product and Energy Act, No. 13 of 1990, as amended).
- The rated capacity of such a tank shall provide sufficient capacity to permit expansion of the product contained therein by the rise in temperature during storage.
- The tank shall be erected at least 3.5 m from buildings, boundaries and any other combustible or flammable materials.
- Adequate precautions shall be provided to prevent spillage during the filling of any tank.
- Soil contaminated by oil, fuel or chemicals shall be removed and disposed of at a registered Hazardous Waste Disposal Site or rehabilitated *in-situ*.
- If larger capacity tanks are required then an acceptable rational design based on a relevant national or international code or standard shall be submitted to the Directorate Energy, Petroleum and Downstream (Ministry of Mines and Energy).

### **3.2.2 Ablution Facilities**

Washing, whether of the person or of personal effects and acts of excretion and urination are strictly prohibited other than at the designated facilities provided. Provision shall thus be made for ablution and washing facilities.

The exact location of the facilities shall be approved by the ESM and Resident Engineer prior to establishment. All temporary portable toilets shall be secured to the ground to prevent them toppling due to wind or any other cause.

Toilets for the workers shall be at a maximum ratio of 1 toilet per 5 workers (preferred 1:15) and be within walking distance of the staff. These facilities shall be maintained in a hygienic state and serviced regularly. Toilet paper shall be provided. The Manager shall ensure that no spillage occurs when the toilets are cleaned or emptied and that the contents are removed from Site. Discharge of waste from toilets into the environment is prohibited.

### **3.2.3 Eating Area**

Bins with lids at the eating areas for his staff shall be provided, which shall be emptied on a daily basis. The waste may be temporarily stored in a facility that is weatherproof and scavenger-proof and which has been approved by the Engineer. The feeding or discarding of food for animals is strictly prohibited.

### **3.2.4 Solid Waste Management**

No burying or dumping of any waste materials, rubble, vegetation or refuse shall occur on Site. A solid waste control and removal system shall be set-up to fit into the larger Project waste management system. The waste may be temporarily stored on Site in a central waste area that is weatherproof and scavenger-proof, and which the ESM and Resident Engineer has approved. The accumulation of construction waste materials must be avoided as far as possible. The system shall comply with the following detailed requirements:

(i) **Dumping**

- Receipts for hazardous waste disposal shall be copied to the ESM and Engineer.
- Refuse shall be disposed of into scavenger- (baboons, dogs, rodents, etc.) and weather-proof bins. The Contractor shall then remove the refuse collected from the working areas, from Site at least once a week or depending on necessity.
- Refuse must be disposed of at an authorized municipal landfill site.

- The Manager shall make provision for workers to clean up the working areas at least once a week.

(ii) Recycling

- Wherever possible, materials used or generated by construction shall be recycled.
- Containers for glass, paper, metals and plastics shall be provided (a four bin recycling system). Office and camp areas are particularly suited to this form of recycling process.
- Where possible and practical, such as at stores and offices, waste shall be sorted for recycling purposes.

### **3.2.5 Waste Water Management**

The Resident Engineer shall set up a contaminated water management system, which shall include collection facilities to be used to prevent pollution, as well as suitable methods of disposal of contaminated water to fit into the larger waste water management system. The Contractor shall prevent the discharge of water contaminated with any pollutants, such as soaps, detergent, cements, concrete, lime, chemicals, glues, solvents, paints and fuels, into the environment. The Contractor shall notify the ESM and Resident Engineer immediately of any pollution incidents on Site.

Water from kitchens, showers, sinks, etc. shall be discharged into a conservancy tank for removal from Site. Runoff from fuel depots/workshops/truck washing areas and concrete swills shall be directed into a conservancy tank and disposed of at an approved municipal hazardous waste site.

Wash areas shall be placed and constructed in such a manner so as to ensure that the surrounding areas are not polluted. This includes, but is not limited to, concrete batching areas, vehicle washing, workshop wash bays, paint wash and cleaning. Wash areas for domestic use shall ensure that the disposal of contaminated water is sanctioned by the ESM.

### **3.2.6 Workshop, Equipment Maintenance and Storage**

Where practical, all maintenance of plant and equipment on Site shall be performed in the workshop. If it is necessary to do maintenance outside of the workshop area, the Contractor shall obtain the approval of the ESM prior to commencing activities.

All equipment shall be kept in good working order and serviced regularly. Equipment shall be removed immediately from the Site and repaired. When the Contractor carries out emergency plant maintenance it is essential that there is no pollution to the environment. This will be overseen by the ESM and Resident Engineer.

The workshop shall have a smooth impermeable (concrete or 250 µm plastic covered with sand) floor, which is bunded and sloped towards an oil trap to contain any spillages. When servicing equipment, drip trays shall be used to collect the waste oil and other lubricants. The floor shall be bunded and sloped towards an oil trap or sump to contain any spillages of substances (e.g. oil). Drip trays shall also be provided in areas for stationary plant (such as compressors) and for "parked" plant (such as scrapers, loaders, vehicles). Drip trays shall be inspected and emptied daily. Drip trays shall be closely monitored during rain events to ensure that they do not overflow. Where practical, the Contractor shall ensure that equipment is covered so that rainwater is excluded from the drip trays.

All washing shall be restricted to a minimum. If essential, washing must be undertaken in the workshop or maintenance areas. The use of detergents for washing shall be restricted to low phosphate and nitrate containing and biodegradable-type detergents. Runoff should be collected, contained and disposed of at an approved municipal hazardous waste site.

**3.3 MITIGATION MEASURES AND PROPOSED MANAGEMENT PROGRAMME**

The table below outlines those specific mitigation measures required in order to fulfil the recommendations. These measures must be implemented during the operational phase of the Kehemu Filling Station. The responsibility for these measures is included in Column 4.

This forms a general code of conduct for all contractors operating on the sight.

While responsibilities have been assigned to various other parties, it must be borne in mind that ultimately the applicant and his/her successor are held responsible for any damage to the environment as a result of the development and that non-compliance with the OEMP will be regarded as non-compliance in terms of the Environmental Authorization.

Issue	Objective	Mitigation Measure	Responsibility	Compliance Notes
<b>PLANNING &amp; DESIGN</b>				
Operator`s Requirements	Ensure that the Site Operator is aware of his/her responsibility.	Provide the contractor with the OEMP.	ESM	Yes. File with EMP and Scoping Assessment Report (July 2021) & ECC (February 2022) available at Manager's Site Office
Environmental Site Manager	Ensure that activities on site are compliant with the requirements of the OEMP.	Appoint an independent Environmental Site Manager to oversee environmental aspects of the development.	New Limit Property Developers CC	
Visuals & Aesthetics	Ensure that the visual aspects of work area are taken into consideration to lessen impacts on neighbouring activities.	Service Station area should be kept neat and tidy at all times. Advert boards on the premises should not obstruct other road users.	Manager	
Waste Management	Ensure the effective and efficient separation, storage and removal of waste from the site.	Develop a Waste Management Plan for the construction phase which will detail: <ul style="list-style-type: none"> <li>Schedules for collection</li> <li>Responsible parties for collection</li> <li>Details regarding waste separation (hazardous vs. general)</li> <li>Provision of facilities for the separation and storage of waste</li> <li>Details regarding the disposal of the waste (hazardous and general)</li> <li>Assigns responsibilities for these activities</li> </ul>	ESM & Manager	
Loss of habitat/eco-systems	Conserve tall indigenous trees.	Indigenous trees should be preserved to recreate and improve some important habitats.	Contractor	

Issue	Objective	Mitigation Measure	Responsibility	Compliance Notes
Training	Improve the awareness of all construction personnel with regard to environmental matters.	Develop and implement a training programme to address environmental issues and responsibilities.	Environmental Site Manager	
Environmental Site Manager and RE	Ensure that there is compliance with the EMP on site.	An Environmental Site Manager may inspect the site at any time during the construction phase.	Environmental Site Manager	
Effect of the EMP	Ensure that the EMP is enforced on all contractors.	Each contractor and subcontractor must be notified on the content of this EMP.	Resident Engineer & Environmental	
Issue	Objective	Mitigation Measure	Responsibility	Compliance Notes
			Site Manager	
Effect of the EMP	Ensure that the EMP is enforced on all contractors	All contractors and subcontractors must be bound by the content and requirements in this EMP.	Resident Engineer & Environmental Site Manager	
Ground Water	Prevent the contamination of groundwater resources.	Vehicles must be equipped with drip trays to prevent spillages of oils and fuels.	Contractor	
Loss of surrounding habitat and sensitive species	Prevent the destruction of protected, medicinal or sensitive plant species.	Protected, medicinal and/or sensitive plants that are likely to be destroyed or affected by construction activities should be relocated to more suitable areas.	Contractor	
Installation of Services	Ensure that all points for water provision are regularly inspected for erosion impacts.	Implement adequate mitigating measures to curtail any erosion impacts.	Contractor	
Installation of Services	Ensure that water used to wash machinery and any other "grey" water does not pollute the site.	Provide a wash bay with a impermeable floor to contain such water.	Contractor	
Litter	Ensure that the site remains clean and clear of litter.	All litter must be collected into rubbish bins located on the site. These bins must be regularly (i.e. weekly) collected and transported to a registered waste disposal facility.	Contractor	
Road Works and Traffic	Ensure that soil does not erode from culverts or similar structures.	All culverts or similar structures must be stabilized with gabions and/or indigenous grasses.	Contractor	
Road Works and Traffic	Ensure that local residents are not inconvenienced by the movement of construction vehicles off-site.	The movement of heavy vehicles from the site must occur outside of peak traffic hours (after 08h30 and before 16h30).	Contractor	
Road Works and Traffic	Ensure that local residents are not inconvenienced	Spillages on the roads should be avoided. When	Contractor	

Issue	Objective	Mitigation Measure	Responsibility	Compliance Notes
	by the movement of construction vehicles off-site.	these occur, they should be cleaned immediately.		
Safety & Security	Ensure the safety and security of staff and the public.	All local authority by-laws must be adhered to.	Manager	
Safety & Security	Ensure the safety and security of staff and the public.	All contractors must take cognisance of and abide by the Occupational Health and Safety Act.	ESM	
Safety & Security	Ensure the safety and security of staff and the public.	Trenches to a depth greater than 1.5 m must be supported or appropriate warning must be provided.	Contractor	
Storage Facilities	Ensure that hazardous materials are stored according to legislative requirements.	Specifically designed storage facilities need to be provided and used for hazardous materials.	Manager & ESM	
Storage Facilities	Ensure that fuel stored on site does not pose a pollution and fire hazard.	Fuels stored on site shall be banded to 110% of the capacity of the largest container.	Contractor & ESM	
Storage Facilities	Ensure that fuel stored on site does not pose a pollution hazard.	The fuel storage area must not be located less than 100m from any water resource.	Contractor & ESM	
Storm Water Run-off	Ensure that run-off does not contribute to erosion & siltation.	Construct and maintain berms on the site to contain storm water run-off or establish riffle beds or retention ponds, as appropriate.	Contractor & ESM	
Vehicle repairs	Ensure that spillages are minimized and that where these occur, that they are appropriately managed.	Minor vehicle repairs on an appropriate work surface may only take place within the provided area.	Manager & ESM	
Waste	Ensure the adequate removal of solid waste.	All wastes (hazardous or general) must be collected and disposed of at an appropriate registered facility.	Contractor	

Issue	Objective	Mitigation Measure	Responsibility	Compliance Notes
Waste	Ensure the adequate management of waste	Refuse shall be disposed of into scavenger- free (stray cats, dogs, rodents, etc.) and weather-proof bins. The Contractor shall then remove the refuse collected from the working areas, from Site at least once a week or depending on necessity. Refuse must be disposed of at an authorized landfill acceptable to the DEA.	Contractor	
Waste	Ensure the adequate management of waste.	No waste should be burnt on site.	Contractor & ESM	
<b>POST CONSTRUCTION</b>				



<b>MONITORING</b>				
Audit Reports	Ensure adequate reporting of progress with the development	Regular reports, monthly and construction end are proposed, and should be forwarded to the DEA.	Environmental Site Manager	
Monitoring	Ensure compliance with the requirements of the EMP.	Undertake monitoring activities on a monthly basis.	Environmental Site Manager	

## **APPENDIX A**

### **ENVIRONMENTAL METHOD STATEMENT**

A method statement forms the baseline information on which sensitive area work takes place and is thus considered a “live document” in that modifications can be negotiated between the Contractor and ESM if or as required. The Contractor (and, where relevant, any subcontractors) must also sign the Method Statement, thereby indicating that the works will be carried out according to the approved methodology. Changes in the methodology must be reflected by amendments to the original approved Method Statement. Amendments must be signed by both the ESM and RE, denoting that the change is environmentally acceptable. The Contractor must also sign the amended Method Statement.

All method statements will form part of the OEMP documentation and are subject to all terms and conditions contained within the OEMP main document.

A Method Statement describes the scope of the intended work in a step-by-step description in order for the ESM or Engineer to understand the Contractor's intentions. This will enable them to assist in devising any mitigation measures, which would minimize environmental impact during these tasks. The Method Statement should also clearly stipulate mitigation methods of the intended works, against which the contractor's performance will be measured.

For each instance wherein it is requested that the Contractor submit a Method Statement to the satisfaction of the ESM and Engineer, the format should clearly indicate the following:-

What a concise, description of the task/work to be undertaken;  
How a detailed description of the process of work, methods, materials and mitigation strategies;  
Where a description/sketch map of the locality of work area (if applicable); and  
When the sequencing of actions with due commencement dates and completion date estimates.

The Contractor must submit the Method Statement two weeks before any particular construction activity is due to start, especially with respect to impacts on sensitive ecosystems. Work may not commence until the method statement has been accepted by the ESM and Engineer, and clearly communicated to the workforce. The Contractor shall, except in the case of emergency activities, allow 14 days for consideration and approval of the Method Statement. The Engineer or ESM may require changes to a Method Statement if the proposal does not comply with the specifications or if, in the reasonable opinion of the Engineer and ESM, the proposal may result in damage to the environment in excess of that permitted by the specifications. Approved Method Statements shall be communicated to all relevant personnel.

Method Statements may be required by the ESM for the following, if so required:

- Construction procedures;
- Materials and equipment to be used;

- How and where materials will be stored;
- The containment of accidental leaks or spills;
- Timing and location of activities; and
- Construction activities
  - o Dust
    - *Dust control protocol.*
  - o Fire and hazardous substances
    - *Handling and storage of hazardous wastes.*
    - *Emergency spillage procedures and compounds to be used.*
    - *Emergency procedures for accidental fire.*
    - *Methods for the disposal of hazardous materials.*
  - o Fuels and fuel spills
    - *Methods of refuelling vehicles.*
    - *Details of methods for fuel spills and cleanup operations.*
  - o Protection of archaeological resources
    - *Methods for dealing with archaeological resources in the event that any are found.*
  - o Protection of environmentally sensitive resources (fauna and flora)
    - *Methods for dealing with conservation areas or areas identified as environmentally sensitive requiring protection.*
    - *Locality and preparation of onsite nursery to house vegetation relocated from construction areas or propagated locally for replanting purposes.*
    - *Details of methods dealing with the identification, transportation and transplanting of flora species of conservation value.*
    - *Details of methods dealing with the identification, capture and relocation of fauna species of conservation value.*

- o Solid waste management
  - *Solid waste control and removal of waste from Site.*
- o Sources of materials
  - *Details of materials imported to the Site (where applicable).*
- o Wash areas
  - *Location, layout, preparation and operation of all wash areas.*
- o Storm water management
  - *Details of how storm water is to be handled on Site.*

A pro-forma Method Statement is given below.

# METHOD STATEMENT

CONTRACT: .....

DATE: .....

**WHAT WORK IS TO BE UNDERTAKEN?** (give a brief description of the works)

**WHERE ARE THE WORKS TO BE UNDERTAKEN?** (where possible, provide an annotated plan and a full description of the extent of works)

**START AND END DATE OF WORKS FOR WHICH THE METHOD STATEMENT IS REQUIRED**

Start Date:

End Date:

**HOW ARE THE WORKS TO BE UNDERTAKEN?** (provide as much detail as possible, including annotated sketches and plans where possible) \*Note: please attach extra pages if more space is required.

## **APPENDIX B**

### **PRO-FORMA: ENVIRONMENTAL MONITORING REPORT**

**PRO-FORMA: ESM ENVIRONMENTAL MONITORING REPORT**

**Zone:** .....

**Environmental Site Manager:**.....

**Report No:**.....

**Date:**.....

Environmental Education	<b>Contractor:</b>	<b>Date undertaken:</b>

Issue	Observation	Remedial action	Compliance
<b>2.1 Construction</b>			
2.1.1 All plant, personnel, etc. restricted to works area?			
2.1.2 Where needed, sensitive areas adequately fenced off?			
2.1.3 Fencing well maintained?			
2.1.4 No unauthorized entry, stockpiling, etc. outside work areas?			
2.1.5 All vehicles and plant remain on designated routes?			
2.1.6 Information posters put up and maintained where needed?			
2.1.7 No smoking in hazardous areas?			
2.1.8 Basic fire fighting equipment available on Site?			
2.1.9 No burning of wastes as a means of disposal?			



Issue	Observation	Remedial action	Compliance
2.1.10 Staff aware of procedures in the event of spills/leaks?			
2.1.11 Materials for dealing with spills/leaks available?			
2.1.11 Emergency contact numbers displayed at Manager's office?			
2.1.12 Complaints Register up to date?			
2.1.13 No animals trapped or harmed?			
2.1.14 No flora removed or damaged outside work areas?			
2.1.15 Adequate drainage and retaining works in place to control erosion/siltation?			
2.1.16 Restricted traffic over stabilized areas?			

Issue	Observation	Remedial action	Compliance
2.1.17 No unauthorized traffic on revegetated areas?			
<b>2.2 Materials</b>			
2.2.1 Materials adequately secured to ensure safe deliveries?			
2.2.2 All materials being stored inside Manager's designated storage area?			
2.2.3 All imported materials free of weeds, litter, etc.?			
2.2.4 No spoil stockpiled outside agreed areas?			

Issue	Observation	Remedial action	Compliance
-------	-------------	-----------------	------------

2.2.5 Spoil stockpiles correctly shaped and protected?			
2.2.6 All plants used for landscaping/rehabilitation listed in the approved plant list?			
2.2.7 Plants adequately protected during transit and at storage facilities?			
2.2.8 Plants healthy and free from diseases and pests?			
<b>2.3 Plant</b>			
2.3.1 Fuel/oil storage facilities adequately secured and protected against leakage?			
2.3.2 Safety signage provided at fuel storage areas?			
2.3.3 All electrical/petrol pumps suitably equipped and placed not cause any danger of ignition?			
2.3.4 Fuel storage areas comply with fire safety regulations?			
2.3.5 Necessary authorizations obtained for temporary above ground fuel tanks?			
2.3.6 Capacity of a fuel tank does not exceed 9000 l?			
2.3.7 Fuel tanks erected at least 3.5 m away from buildings, boundaries or other flammable materials?			
2.3.8 Adequate toilet facilities provided for staff (min. 1 toilet per 5 workers)?			
2.3.9 Toilets adequately maintained?			
2.3.10 All workers use toilets?			
2.3.11 Scavenger-proof bins with lids provided at eating areas?			

Issue	Observation	Remedial action	Compliance
2.3.12 Waste temporarily stored inside Contractor's Camp in weather- and scavenger-proof bins?			
2.3.13 No burying or dumping of wastes on site?			
2.3.14 Waste management system in place?			
2.3.15 Refuse disposed of at licensed landfill?			
2.3.16 Adequate waste-water management system in place?			
2.3.17 Approval for discharge of contaminated water into municipal sewer system?			
2.3.18 Runoff from workshops, fuel depots, etc. directed into conservancy tanks for disposal at approved site?			
2.3.19 Wash areas placed and built in such a way that does not cause any pollution?			
2.3.20 All maintenance of plant and equipment takes place in workshop?			
2.3.21 All plant is well maintained (no leaking)?			
2.3.22 Workshop has a bunded, impermeable floor sloping towards oil trap?			
2.3.23 Filling Station area tidy?			
2.3.24 All plant and machinery have drip trays, which are checked and emptied daily?			
2.3.25 All repairs on machinery using fuels or lubricants done over a drip tray?			
2.3.26 Static plant located within a bunded area?			
2.3.27 Measures in place to minimize dust generation?			

